

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate of quantities for restoring the Puligarkota tank, Registered No. 144 of Srinivaspur Taluk.

	Per	Quantity
Bund—		
Earthwork with proper consolidation (deducting revetment)	C. yd.	5,648
Turfing	S. yd.	9,619
New stone work with paper jelly packing, etc.	C. yd.	1,813
Old stone work with new jelly packing, etc.		599
Fixing grade stones with figures cut and painting	No.	29
Index stones with top width number cut and painted		29
Gauge stone		1
Date stone		1
Registered No. stone		1
B. M. stones		2
Jungle clearing	Lump sum	
Weir—		
Constructing weir at left side 120 in length at R. L. 57'00—		
Earthwork excavation and using the same to bund	C. yd.	2,023
Concrete in surki mortar	C. ft.	891
Burnt brick in surki mortar		1,535
Burnt stone slabs dressed	S. ft.	418
Surki plastering	Sqr.	19'55
Joggle stones	No.	40
New stone work for apron wings, etc.	C. yd.	341
Pointing to slabs over body walls and toe walls	Sqr.	3'60
Sluice—		
Repairing No. 1 sluice	Lump sum	
Constructing a new sluice at C. S. 34 at the site of existing old sluice sill level R. L. 43'35—		
Earthwork excavation and refilling the same with proper consolidation	C. yd.	110
Concrete in surki mortar	C. ft.	164
Burnt brick in surki mortar		581
Burnt stone slabs dressed	S. ft.	323
Surki plastering	Sqr.	4'00
Removing and refixing old gibbet stones	Lump sum	
Cutting upper and lower orifices grooves in gibbet stones, etc.		
Teakwood plug with iron rods including locking arrangements		
Bailing water if necessary		
Blocking up the sluice at C. S. 37		

V. V. KARVE,
Executive Engineer.

TUMKUR DIVISION.

Abstract Notification.

Attention is invited to the notice calling for tenders for improving Pothaganahalli Tank, Tumkur Taluk, near Mavathur, published in Part IV of *Mysore Gazette*, dated 24th January 1918, pages 86—87.

The last date for tender is 15th February 1918.

Dated 24th January 1918.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer Tumkur Division, up to 20th February 1918, for constructing Anglo-Vernacular School at Maddagiri. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1919.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Tumkur between the hours of 11 A.M. to 5 P.M. except on Sundays and Government Holidays.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 300 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing Anglo-Vernacular School at Maddagiri" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason, whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract.

No.	Item of work	Per	Quantity
1	Earthwork excavation and filling in basement	C. ft.	165
2	Metal concrete in mortar	"	2,935
3	Stone in mortar, foundation and basement	"	3,134
4	Burnt brick in clay, superstructure	"	6,205
5	Do chunam do	"	1,299
6	Do do do arch work	"	284
7	Burnt stone slabs dressed and fixed	S. ft.	906
8	Plastering with chunam	Sq.	140'17"
9	White and color washing	"	140'17"
10	Teakwood panelled doors	S. ft.	480
11	Teakwood panelled windows with glazed shutters, etc.	"	435
12	Teakwood rectangular ventilators glazed	"	96
13	Teakwood circular ventilators glazed	"	124
14	Silicate painting	Sq.	24'66"
15	Cut stone pillars, two times dressed with base caps, etc.	No.	16
16	Brick masonry half pillars with base caps, etc.	"	6
17	Teakwood work wrought and put up	C. ft.	249'60"
18	Ridge tiles set in mortar and pointed	R. ft.	203
19	Roofing with 1st class Mangalore tiles over teak reapers, etc.	Sq.	53'17"
20	Flooring with Cuddappah slabs for verandah and Mangalore tiles for rooms over 3" concrete and cement pointing.	"	27'87"
21	Flooring with 1 1/2 ft. sq. Shabavud slabs laid diagonally 1 1/2" thick over 3" concrete and cement pointing.	"	5'40"
22	Chunam borders	R. ft.	112
23	Ionic entablature	"	65
24	Cornices 12" thick	"	500
25	Preparing ionic and dorio capitals	No.	13
26	Do bases	"	18
27	Moulded archivolts	R. ft.	31
28	Preparing rectangular and circular panels, ornamental, flower works, etc.	Lump sum	"
29	Clearing site and levelling ground, etc.	"	"
30	Teakwood ornamental eave boards 1" thick	R. ft.	153
31	Teakwood planking 1" thick	S. ft.	211
32	Zinc sheet for valleys	"	211
33	Tarring wood work and wood oiling	Sq.	20'00"
34	Wrought iron trusses	Cwts.	6 1/2
35	Teakwood panelled screen	S. ft.	166
36	Forming approach road	Lump sum	"

Dated 25th January 1918.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Tumkur Division, up to 25th February 1918, for restoring Bathalli tank, Registered No. 96-188 of Hubridurga Sammat, Kunigal Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1919.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Tumkur between the hours of 11 A. M. and 5 P. M., except Sundays and holidays.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees (200) two hundred only in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Bathalli tank, Registered No. 96-188, Kunigal Taluk, in default of which, tenders will be rejected."

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate showing the quantities for restoring Bettahalli tank, Registered No. 96—188 of Hutridrug Sammat, Kunigal Taluk.

No.	Items of work	Per	Quantity	Rate
<i>Bund.</i>				
1	Earthwork to bund including watering and tamping ...	C. yd.	7,824	
2	Cutting bund for filling in breach and earth to be used for bund ...	"	1,667	
3	Breach filling including watering and tamping ...	"	6,493	
4	Cutting steps and grips in the old bund at breach for joining the new earthwork with old bund and bailing water, etc.	Lump sum	Rs.	
5	Old stone work with new jelly ...	C. yd.	360	
6	New stone work ...	"	428	
7	Gravel backing behind new stone work ...	"	165	
8	Turning ...	S. yd.	6,330	
9	Providing new grade stones with cutting figures and painting, etc., with bed slabs.	No.	21	
10	Providing new B. M. stones with cutting figures and painting, etc.	"	2	
11	Providing registered number stone with cutting figures and painting, etc.	"	1	
12	Jungle clearing and removing roots wherever necessary.	Lump sum	Rs.	
Total				
<i>Sluice.</i>				
1	Repairing the existing sluice after examining the leakage	Lump sum	Rs.	
Total				
<i>No. 1 Left wasteh weir 100 ft. long.</i>				
1	Cutting slips and loose earth from the breach, etc.	Lump sum	Rs.	
2	Breach filling with fine gravel including watering and tamping.	C. yd.	111	
3	Burnt brick in surki mortar	C. ft.	674	
4	Burnt stone slabs, dressed	S. ft.	250	
5	Surki plastering	Sq.	330	
6	New rough stone work	C. yd.	94	
7	Jelly wedging to crevices and holes in the old apron	"	40	
8	Resetting old stone work with new jelly	"	15	
9	Earthwork to wing walls, etc.	"	100	
Total				
<i>Waste weir No. 2, 51 ft. long.</i>				
1	Dismantling a portion of apron at front and excavating foundation to body wall	Lump sum	Rs.	
2	Burnt brick in surki mortar	C. ft.	288	
3	Burnt stone slabs, dressed	S. ft.	85	
4	Surki plastering	Sq.	139	
5	Rough stone work to wing wall	C. yd.	15	
6	Earthwork to wing walls, etc.	"	80	
Total				
Grand Total				

Dated 26th January 1918.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Tumkur Division, up to 20th February 1918, for constructing wards and kitchen in the compound of Civil Hospital, Tumkur. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1919.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Tumkur, between the hours of 11 A.M. and 5 P.M.; except Sundays and Government holidays.

3. Tenders should be submitted on printed forms, which may be obtained from the Executive Engineer. The tender should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees three hundred only (Rs. 300), in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing wards and kitchen in the compound of Civil Hospital, Tumkur," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office, in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate showing the quantities for constructing wards and kitchen in the Civil Hospital compound at Tumkur.

No.	Items of work	Per	Quantity	
			Wards	Kitchen
1	Earthwork excavation and filling in basement	C. yd.	78	9
2	Concrete with burnt stone in chunam	C. ft.	441	...
3	Burnt stone in mortar	"	2,618	...
4	Burnt stone in mud	"	...	318
5	Burnt brick in mortar	"	3,941	112
6	Burnt brick in mud	"	...	516
7	Archwork brick in mortar	"	...	10
8	Burnt stone slabs	S. ft.	766	23
9	Plastering with mortar	Sqr.	59'33	11'66
10	White and color washing	"	59'33	11'66
11	Teakwood work wrought and put up with wood oiling	C. ft.	127	18'47
12	Teakwood doors panelled with iron works, etc., complete	S. ft.	254	18
13	Teakwood battened doors with iron works, etc., complete	"	81	...
14	Teakwood windows with bolt panelled and glazed shutters with iron bars, etc., complete	"	...	6
15	Teakwood windows with battened shutters and iron work, etc.	"	101	...
16	Teakwood ventilators with glazed shutters, iron works, etc.	"	72	...
17	Teakwood shelves with panelled shutters, iron works, etc.	Sqr.	23'05	2'07
18	Roofing with 1st class Mangalore tiles over teak reapers, etc.	R. ft.	84	12
19	Ridge tiles set in mortar	No.	9	...
20	Burnt stone pillars with base and capitals	R. ft.	167	41
21	Ornamental eave boards	"
22	Teakwood plain eave board	"	...	35
23	Cornice 1' thick including plastering	"	147	...
24	Dwarf wall over gable ends including finials	"	132	...
25	Flooring with 1st class Mangalore tiles over 8" concrete and cement pointing	Sqr.	6'27	...
26	Flooring with Cuddappa slabs on 3" concrete bed and cement pointing	"	6'02	1'18
27	Constructing sink with iron pipe, etc.	Lump	sum Rs.	...
28	Chunam border	R. ft.	...	15
29	Terracing	Sqr.	...	0'46
30	Constructing drains to lead off water from bath and latrine	Lump	sum	...
31	Chacolate painting	Sqr.	12'82	0'48
32	Clearing site and levelling ground	Lump	sum Rs.	...
33	Teakwood planks with zinc sheets for valleys	S. ft.	156	...
34	Pointing to basement	Sqr.	5'00	0'55
35	Mortar pestal stone	Lump	sum Rs.	...

N. G. KRISHNA IYENGAR,
Executive Engineer.

DEPARTMENT OF INDUSTRIES AND COMMERCE.

SUPPLY OF TOOLS.

Notice is hereby given, that sealed tenders will be received at the office of the Director of Industries and Commerce up to 12 noon, 18th February 1918 for the supply of tools required for the Department. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of March 1918.

2. Tenders should be submitted on printed forms which may be obtained from the Director. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

3. Each tender must be accompanied by a deposit of Rs. 200 in cash as earnest money and be superscribed "Tender for supply of tools required for the Department of Industries and Commerce"; in default of which tenders will be rejected.

4. The final acceptance of any tender will rest with the Director who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

5. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled and his earnest money will be forfeited.

6. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Director's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

7. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.